

5211 TOILET UNIT, with 3 cabins, prefabricated flat pack, for sewer connection

Prefabricated flat pack toilet container with 3 toilet cubicles for assembly on-site. Fully assembled size approx. L3900 x W1500 x H2450 mm

Features/construction:

- Modular construction allowing for disassembly and reassembly
- Suitable for set up on smooth/flat ground (e.g. gravel)
- Smooth and easy to clean/disinfect cabin surface inside and outside
- Withstands any deformations between -30 and +60° C
- Resists windspeeds up to 80km/h
- Sound and thermal insulated construction
- Electric instantaneous water heater with temperature control, plugged into socket with main switch
- 160-200W solar panel for optional power supply (lighting and sockets)
- Toilet cubicle:
 - o 1 x wash basin, 1 x water closet for sitting and 1 x shower hose for anal cleansing (taps optimized for water saving)
 - o 1 x mirror
 - o 1 x window
 - o 1 x CEE 7/3 socket
 - o LED lighting with switch (inside)

Water inlet: hot and cold water connection with compression coupling to fit 32 mm MDPE pipe

Waste water outlet: DRAIN/SEWER PIPE, DN110, PVC-U

Electrical connection: CEE 400V 5p 16A IP44/IP54 plug to connect to grid/generator

Additionally supplied with:

- All needed accessories for set-up (e.g. fittings, internal pipework, electric cables, ground anchors) and spare parts for 1 year of operation/maintenance
-